



**-Proposal-**

Tue Oct 17 2023

Dear \_\_\_\_\_, thank you for your inquiry on a new building to be built by Fetterville Pole Buildings. Below are listed the specifications on which the price is based:

Free Standing Building installed on your level site  
28' width x 56' length x 10' inside height  
Roof System: 4' o/c trusses Pitch: 4/12 Loading: 30-5-5 standard  
Walls: 8' o/c 3-Ply 2x6 Glulam Load-Bearing Posts  
Siding: 26 Gauge Painted Steel (Undecided Color) (Lifetime Warranty)  
Trim Color (Undecided Color) (Lifetime Warranty)  
Roofing Type: 26 Gauge Painted Steel with Ridge Vent (Undecided Color) (Lifetime Warranty)  
Overhangs: 12" Boxed Vented on 2-eaves (Undecided Color) soffit and fascia  
1 - 3' X 6'8" Steel Flush Entry Door  
3 - 36" x 44" Single Hung Insulated w/ Half Screen Window  
2 - 12X12 #2 Horse Stall 8' Walls with 2 - window grills  
1 - 8 x 16 Non-Insulated Tack Room 8' Walls w/Door & Ceiling  
1 - 8 x 8 Feed Room w/ 8' Walls  
280 - Post-Frame Dividing Wall w/1 Side Finished  
\_\_\_\_Lean-to 10 x 32 x 10 Open On Eave Lean-to with 2/12 pitch  
Roofing Type: 27 Gauge Painted Steel (Undecided Color)  
Overhangs: 12" Boxed Vented on 1-eave & 2-gables (Undecided Color) soffit and fascia

The cost for this project is \$46,000.

This price is good for 15 days from the date of this letter. Thank you and if I can be of any further assistance please feel free to call.

Sincerely,  
Larry Gill  
Fetterville Pole Buildings  
Phone 570-556-7369

Additional available options \*:

- + Add Walls: Smart Post Option for \$3,210.
- + Add Insulation/Underlayment: Radiant Insulation Barrier on Roof for \$1,565.
- + Add 1 - 2' Cupola, Vented and a Standard Black weathervane for \$793.
- + Add Liner Panel: 29 gauge painted steel Liner Panel on Ceiling for \$2,302.